

Mt Charlton to Ramsay Creek Pipeline Upgrade

Project Description:	The 600 mm diameter mild steel pipeline from Mount Charlton to Rockhampton was originally constructed in the mid 1920s and later modified in the 1950s as the water supply to Rockhampton. The pipeline is now used to provide water to The Caves area from Rockhampton. The pipeline is exhibiting signs of major corrosion in a number of areas and repairs have been undertaken as leaks occur. This project is to refurbish the most significant sections of pipeline.
Reasons for Project:	The refurbishment of the worst sections of the pipeline will reduce the need for reactive maintenance and provide a better level of water security to the consumers and reduce the loss of water.
Benefits of Project:	To reduce the incidences of emergency repair work and the consequent loss of treated water.
Estimated Total Cost:	\$332,800
Commencement Date:	November 2019
Duration of Project:	Six (6) months
Contact Officer:	Scott Casey, Manager Water and Waste Operations
Potential Interruptions:	Minor water supply interruptions to consumers may be experienced.